

GENERAL NOTES

1. ALL WORK AND MATERIALS MUST BE IN ACCORDANCE WITH THE CURRENT VERSION OF THE SILVER LAKE WATER & SEWER DISTRICT STANDARDS PER DISTRICT CODE CHAPTER 6.20.
2. PRIOR TO CONSTRUCTION OF THE WATER AND SEWER SYSTEMS, THE CONTRACTOR SHALL CONTACT THE SILVER LAKE WATER & SEWER DISTRICT FOR A PRECONSTRUCTION MEETING.
3. LOCATIONS SHOWN OF EXISTING UTILITIES AND IMPROVEMENTS ARE APPROXIMATE ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXACT LOCATIONS OF ALL UTILITIES AND IMPROVEMENTS TO AVOID DAMAGE OR DISTURBANCE.
4. CONTRACTOR SHALL CALL "DIAL A DIG" AT 811 TWO FULL WORKING DAYS PRIOR TO CONSTRUCTION FOR AID IN LOCATING ANY EXISTING UNDERGROUND UTILITIES.
5. RIGHT-OF-WAY RESTORATION SHALL BE IN ACCORDANCE WITH THE APPLICABLE STANDARDS OF THE PERMITTING AGENCY.
6. THE CONTRACTOR SHALL KEEP TWO SETS OF PLANS ON SITE AT ALL TIMES FOR RECORDING "AS BUILT" INFORMATION. AS-BUILT PLANS SHALL BE SUBMITTED TO SILVER LAKE WATER & SEWER DISTRICT AT COMPLETION OF CONSTRUCTION.
7. PRIVATELY MAINTAINED BACKFLOW PREVENTION SHALL BE INSTALLED PER DISTRICT CODE CHAPTER 6.20, ARTICLE V, COMMENSURATE WITH THE ASSESSED DEGREE OF HAZARD AS DETERMINED BY THE DISTRICT.

SILVER LAKE WATER & SEWER DISTRICT
APPROVED FOR CONSTRUCTION

BY: _____ DATE: _____
DISTRICT OFFICIAL

DISTRICT PROJECT NUMBER: _____

"THESE PLANS ARE APPROVED FOR CONSTRUCTION FOR THE PERIOD NOTED ON THE DEVELOPER EXTENSION AGREEMENT. THE DISTRICT RESERVES THE RIGHT TO MAKE REVISIONS, MODIFICATIONS, AND CHANGES SHOULD CONSTRUCTION BE DELAYED BEYOND THIS TIME LIMIT."